
# **SDN-PRACTICAL**

# **Practical No.8: Implement IP Sec Site -to -Site VPNs**

# **Step 1: Design the network topology.**



Step 2: Configure the network.

Router 1 (R1):

```
down
R1#
R1#config t
Enter configuration commands, one per line. End with CNTL/Z.
R1(config)#no ip domain lookup
R1(config)#line con 0
R1(config-line)#logging synch
R1(config-line)#exec-timeout 0 0
R1(config-line)#exit
R1(config)##this is id R1, Implement GRE over IPsec site to site VPN#
R1(config)#int f0/0
R1(config-if)#description connection to R2
R1(config-if)#ip add 64.100.0.2 255.255.255.252
R1(config-if)#no shut
R1(config-if)#ex
R1(config)#
*Mar 1 00:03:59.407: %LINK-3-UPDOWN: Interface FastEthernet0/0, changed state to up
*Mar 1 00:04:00.407: %LINEPROTO-5-UPDOWN: Line protocol on Interface FastEthernet0/0, changed
state to up
R1(config)#int f0/1
R1(config-if)#description connection to D1
R1(config-if)#ip add 10.10.0.1 255.255.255.252
R1(config-if)#no shut
R1(config-if)#ex
R1(config)#
*Mar 1 00:04:31.371: %LINK-3-UPDOWN: Interface FastEthernet0/1, changed state to up
*Mar 1 00:04:32.371: %LINEPROTO-5-UPDOWN: Line protocol on Interface FastEthernet0/1, changed
state to up
R1(config)#router ospf 123
R1(config-router)#router-id 1.1.1.1
R1(config-router)#auto-cost reference-bandwidth 1000
% OSPF: Reference bandwidth is changed.
         Please ensure reference bandwidth is consistent across all routers.
R1(config-router)#network 10.10.0.0 0.0.0.3 area 0
R1(config-router)#default-information originate
R1(config-router)#exit
R1(config)#ip route 0.0.0.0 0.0.0.0 64.100.0.1
R1(config)#end
R1#
*Mar 1 00:06:19.803: %SYS-5-CONFIG_I: Configured from console by console
R1#
```

#### R2:

```
R2#conf t
Enter configuration commands, one per line. End with CNTL/Z.
R2(config)#no ip domain lookup
R2(config)#line con 0
R2(config-line)#logging synch
R2(config-line)#exec-timeout 0 0
R2(config-line)#exit
R2(config)#$ $This is R2, Implement GRE over IPSec site-to-site$
% Invalid input detected at '^' marker.
R2(config)## This is R2, Implement GRE over IPSec site-to-site#
R2(config)#int f0/0
R2(config-if)#description connection to R1
R2(config-if)#ip add 64.100.0.1 255.255.255.252
R2(config-if)#no shut
R2(config-if)#ex
R2(config)#
 *Mar 1 00:06:03.423: %LINK-3-UPDOWN: Interface FastEthernet0/0, changed state to up
*Mar 1 00:06:04.423: %LINEPROTO-5-UPDOWN: Line protocol on Interface FastEthernet0/0, changed state to up
*Mar I 00:00:04:423. %EINER(0:05 3 0:05)
R2(config)#int f0/1
R2(config-if)#description connection to R3
R2(config-if)#ip add 64.100.1.1 255.255.255.252
R2(config-if)#no shut
R2(config-if)#ex
R2(config)#
 *Mar 1 00:06:39.111: %LINK-3-UPDOWN: Interface FastEthernet0/1, changed state to up
*Mar 1 00:06:40.111: %LINEPROTO-5-UPDOWN: Line protocol on Interface FastEthernet0/1, changed state to up
*Mar 1 00:06:40.111: %LINEPROTO-5-UPDOWN: Line protocol on Interface FastEthernet0/1, changed state R2(config)#int L0
R2(config-if)#descrip
*Mar 1 00:06:50.547: %LINEPROTO-5-UPDOWN: Line protocol on Interface Loopback0, changed state to up R2(config-if)#description internet simulated address
R2(config-if)#ip add 209.165.200.225 255.255.255.224
R2(config-if)#exit
R2(config)#ip route 0.0.0.0 0.0.0.0 loopback 0
R2(config)#ip route 10.10.10.0.0 255.255.252.0 64.100.0.2
% Invalid input detected at '^' marker.
R2(config)#ip route 10.10.0.0 255.255.252.0 64.100.0.2
R2(config)#ip route 10.10.4.0 255.255.252.0 64.100.1.2
R2(config)#ip route 10.10.16.0 255.255.248.0 64.100.1.2
R2(config)#end
R2#
 *Mar 1 00:09:28.951: %SYS-5-CONFIG_I: Configured from console by console
```

#### R3:

```
R3#conf t
Enter configuration commands, one per line. End with CNTL/Z.
R3(config)#line con 0
R3(config-line)#logging sync
R3(config-line)#exec-timeoute 0 0
% Invalid input detected at '^' marker.
R3(config-line)#exec-timeout 0 0
R3(config-line)#exit
R3(config)##this is R3, implement GRE over IPSec site-to-site VPN#
R3(config)#int f0/0
R3(config-if)#description connection to R2
R3(config-if)#ip add 64.100.1.2 255.255.255.252
R3(config-if)#no shut
R3(config-if)#ex
R3(config)#
*Mar 1 00:10:21.787: %LINK-3-UPDOWN: Interface FastEthernet0/0, changed state to up
*Mar 1 00:10:22.787: %LINEPROTO-5-UPDOWN: Line protocol on Interface FastEthernet0/0, changed
state to up
R3(config)#int f0/1
R3(config-if)#description connection to D2
R3(config-if)#ip add 10.10.4.1 255.255.255.252
R3(config-if)#no shut
R3(config-if)#exi
R3(config)#
*Mar 1 00:11:11.759: %LINK-3-UPDOWN: Interface FastEthernet0/1, changed state to up
*Mar 1 00:11:12.759: %LINEPROTO-5-UPDOWN: Line protocol on Interface FastEthernet0/1, changed
state to up
R3(config)#ip route 0.0.0.0 0.0.0.0 64.100.1.1
R3(config)#router ospf 123
R3(config-router)#router-id 3.3.3.1
R3(config-router)#auto-cost reference-bandwidth 1000
% OSPF: Reference bandwidth is changed.
        Please ensure reference bandwidth is consistent across all routers.
R3(config-router)#network 10.10.4.0 0.0.0.3 area 0
R3(config-router)#default-information originate
R3(config-router)#exit
R3(config)#end
R3#
*Mar 1 00:13:05.515: %SYS-5-CONFIG_I: Configured from console by console
```

## Router 4 (D1):

```
D1#conf t
Enter configuration commands, one per line. End with CNTL/Z.
D1(config)#no ip domain lookup
D1(config)#line con 0
D1(config-line)#logging synch
D1(config-line)#exec-timeout 0 0
D1(config-line)#exit
D1(config)##this is D1, Implement GRE over IPSec site-to-site VPN#
D1(config)#int f0/0
D1(config-if)#description connection to R1
D1(config-if)#ip add 10.10.0.2 255.255.255.252
D1(config-if)#no shut
D1(config-if)#ex
D1(config)#
*Mar 1 00:15:02.195: %LINK-3-UPDOWN: Interface FastEthernet0/0, changed state to up
*Mar 1 00:15:03.195: %LINEPROTO-5-UPDOWN: Line protocol on Interface FastEthernet0/0, changed state to up
D1(config)#int f0/1
D1(config-if)#description connection to PC1
D1(config-if)#ip add 10.10.1.1 255.255.255.0
D1(config-if)#no shut
D1(config-if)#exit
D1(config)#
*Mar 1 00:15:32.151: %LINK-3-UPDOWN: Interface FastEthernet0/1, changed state to up
*Mar 1 00:15:33.151: %LINEPROTO-5-UPDOWN: Line protocol on Interface FastEthernet0/1, changed state to up
D1(config)#int L2
D1(config-if)#no shut

*Mar 1 00:15:39.023: %LINEPROTO-5-UPDOWN: Line protocol on Interface Loopback2, changed state to up
D1(config-if)#description loopback to simulate an ospf network
D1(config-if)#ip add 10.10.2.1 255.255.255.0
D1(config-if)#ip ospf network point-to-point
D1(config-if)#exit
D1(config)#int L3
D1(config-if)#i
*Mar 1 00:16:46.283: %LINEPROTO-5-UPDOWN: Line protocol on Interface Loopback3, changed state to up D1(config-if)#ip ospf network point-to-point
D1(config-if)#description loopback to simulate an OSPF network D1(config-if)#ip add 10.10.3.1 255.255.255.0
D1(config-if)#ip ospf network point-to-point
D1(config-if)#exit
D1(config)#router ospf 123
D1(config-router)#router-id 1.1.1.2
D1(config-router)#auto-cost reference-bandwidth 1000
% OSPF: Reference bandwidth is changed.
Please ensure reference bandwidth is consistent across all routers.
D1(config-router)#network 10.10.0.0 0.0.3.255 area 0
D1(config-router)#exit
D1(config)#end
D1#
         1 00:19:06.907: %SYS-5-CONFIG_I: Configured from console by console
*Маг
D1#
         1 00:19:08.975: %OSPF-5-ADJCHG: Process 123, Nbr 1.1.1.1 on FastEthernet0/0 from LOADING to FULL, Loading Done
```

# Router 5 (D2):

```
D2#
D2#conf t
Enter configuration commands, one per line. End with CNTL/Z.
Enter configuration commands, one per line. End with CNTL/Z.
D2(config)#no ip domain lookup
D2(config)#line con 0
D2(config-line)#logging synch
D2(config-line)#exec-timeout 0 0
D2(config-line)##this is D2, implement GRE over IPSec site-to-site VPN#
D2(config-line)#int f0/0
D2(config-if)#description connection to R3
D2(config-if)#ip add 10.10.4.2 255.255.255.0
D2(config-if)#no shut
D2(config-if)#
*Mar 1 00:19:45.223: %LINK-3-UPDOWN: Interface FastEthernet0/0, changed state to up
*Mar 1 00:19:46.223: %LINEPROTO-5-UPDOWN: Line protocol on Interface FastEthernet0/0, changed state to up
D2(config-if)#exit
D2(config)#int f0/0
D2(config-if)#description connection to R3
D2(config-if)#ip add 10.10.4.2 255.255.255.252
D2(config-if)#no shut
D2(config-if)#ex
D2(config)#int f0/1
D2(config-if)#ip add 10.10.5.1 255.255.255.0
D2(config-if)#no shut
D2(config-if)#exit
D2(config)#
*Mar 1 00:21:39.139: %LINK-3-UPDOWN: Interface FastEthernet0/1, changed state to up
*Mar 1 00:21:40.139: %LINEPROTO-5-UPDOWN: Line protocol on Interface FastEthernet0/1, changed state to up
D2(config)#int loopback 16
D2(config-if)#
 Mar  1 00:21:48.671: %LINEPROTO-5-UPDOWN: Line protocol on Interface Loopback16, changed state to up
Page 1 00:21:48.071: %LINEPROTO-3-UPDOWN: Line protocol on Int D2(config-if)#description loopback to simulate an ospf network D2(config-if)#ip add 10.10.16.1 255.255.255.0 D2(config-if)#ip ospf network point-to-point D2(config-if)#ext
D2(config)#int loopback 16
D2(config-if)#ex
D2(config)#int L17
D2(config-if)#ip ospf network point-to-point
*Mar 1 00:23:12.335: %LINEPROTO-5-UPDOWN: Line protocol on Interface Loopback17, changed state to up
D2(config-if)#description loopback to simulate an ospf network
D2(config-if)#ip add 10.10.17.1 255.255.255.0
D2(config-if)#ip ospf network point-to-point
D2(config-if)#ex
```

```
D2(config)#int L18
D2(config-if)#description loopback to simulate an ospf network
*Mar 1 00:23:44.487: %LINEPROTO-5-UPDOWN: Line protocol on Interface Loopback18, changed state to up D2(config-if)#description loopback to simulate an ospf network
D2(config-if)#ip add 10.10.18.1 255.255.255.0
D2(config-if)#ip ospf network point-to-point
D2(config-if)#ex
D2(config)#int L19
D2(config-if)#
Mar  1 00:24:17.087: %LINEPROTO-5-UPDOWN: Line protocol on Interface Loopback19, changed state to up
D2(config-if)#description loopback to simulate an ospf network
D2(config-if)#ip add 10.10.19.1 255.255.255.0
D2(config-if)#ip ospf network point-to-point
D2(config-if)#ex
D2(config)#int L20
D2(config-if)#ip add 10.10.19.1 255.255.255.0
Mar 1 00:24:45.755: %LINEPROTO-5-UPDOWN: Line protocol on Interface Loopback20, changed state to up*
D2(config-if)#description loopback to simulate an ospf network
D2(config-if)#ip add 10.10.20.1 255.255.255.0
D2(config-if)#ip ospf network point-to-point
D2(config-if)#ex
D2(config)#int L21
D2(config-if)#
Mar 1 00:25:11.391: %LINEPROTO-5-UPDOWN: Line protocol on Interface Loopback21, changed state to up*
D2(config-if)#description loopback to simulate an ospf network
D2(config-if)#ip add 10.10.21.1 255.255.255.0
D2(config-if)#ip ospf network point-to-point
D2(config-if)#ex
D2(config)#
D2(config)#int L22
D2(config-if)#
Mar  1 00:25:45.531: %LINEPROTO-5-UPDOWN: Line protocol on Interface Loopback22, changed state to up
D2(config-if)#description loopback to simulate an ospf network D2(config-if)#ip add 10.10.22.1 255.255.255.0
D2(config-if)#ip ospf network point-to-point
D2(config-if)#ex
D2(config)#int L23
D2(config-if)#
Mar 1 00:26:22.339: %LINEPROTO-5-UPDOWN: Line protocol on Interface Loopback23, changed state to up:
D2(config-if)#description loopback to simulate an ospf network
D2(config-if)#ip add 10.10.23.1 255.255.255.0
D2(config-if)#ip ospf network point-to-point
D2(config-if)#ex
D2(config)#router ospf 123
D2(config-router)#router-id 3.3.3.2
D2(config-router)#auto-cost reference-bandwidth 1000
% OSPF: Reference bandwidth is changed.
         Please ensure reference bandwidth is consistent across all routers.
D2(config-router)#network 10.10.4.0 0.0.1.255 area 0
D2(config-router)#network 10.10.4.0 0.0.1.255 area 0
D2(config-router)#network 10.10.4.0 0.0.1.255 area 0
*Mar 1 00:27:53.487: %OSPF-5-ADJCHG: Process 123, Nbr 3.3.3.1 on FastEthernet0/0 from LOADING to FULL, Loading Done
D2(config-router)#network 10.10.16.0 0.0.7.255 area 0
D2(config-router)#exit
D2(config)#end
D2#
      1 00:28:16.943: %SYS-5-CONFIG I: Configured from console by console
*Mar
```

## PC 1:

```
PC1> ip 10.10.1.10/24 10.10.1.1
Checking for duplicate address...
PC1 : 10.10.1.10 255.255.255.0 gateway 10.10.1.1
PC1> sh ip
NAME
            : PC1[1]
IP/MASK
           : 10.10.1.10/24
GATEWAY
            : 10.10.1.1
DNS
MAC
            : 00:50:79:66:68:00
LPORT
           : 10032
RHOST:PORT : 127.0.0.1:10033
MTU
            : 1500
PC1>
```

### PC 2:

```
PC2> ip 10.10.5.10/24 10.10.5.1
Checking for duplicate address...
PC2 : 10.10.5.10 255.255.255.0 gateway 10.10.5.1
PC2> sh ip
           : PC2[1]
NAME
IP/MASK
           : 10.10.5.10/24
           : 10.10.5.1
GATEWAY
DNS
MAC
           : 00:50:79:66:68:01
LPORT
           : 10034
RHOST:PORT : 127.0.0.1:10035
MTU
            : 1500
PC2>
```

Step 3: On PC1, verify end-to-end connectivity.

From PC1, ping the first loopback on D3 (10.10.16.1).

```
PC1> ping 10.10.16.1

84 bytes from 10.10.16.1 icmp_seq=1 ttl=251 time=56.074 ms

84 bytes from 10.10.16.1 icmp_seq=2 ttl=251 time=59.328 ms

84 bytes from 10.10.16.1 icmp_seq=3 ttl=251 time=61.858 ms

84 bytes from 10.10.16.1 icmp_seq=4 ttl=251 time=50.671 ms

84 bytes from 10.10.16.1 icmp_seq=5 ttl=251 time=49.766 ms
```

Finally, from PC1, ping the default gateway loopback on R2 (209.165.200.225).

```
PC1> ping 209.165.200.225

84 bytes from 209.165.200.225 icmp_seq=1 ttl=253 time=30.170 ms

84 bytes from 209.165.200.225 icmp_seq=2 ttl=253 time=30.389 ms

84 bytes from 209.165.200.225 icmp_seq=3 ttl=253 time=29.850 ms

84 bytes from 209.165.200.225 icmp_seq=4 ttl=253 time=31.259 ms

84 bytes from 209.165.200.225 icmp_seq=5 ttl=253 time=21.841 ms
```

Step 4: Verify the routing table of R1 and R3.

Verify the OSPF routing table of R1.

```
R1#sh ip route ospf
10.0.0.0/8 is variably subnetted, 4 subnets, 2 masks
0 10.10.1.0/24 [110/200] via 10.10.0.2, 01:36:40, FastEthernet0/1
0 10.10.2.0/24 [110/101] via 10.10.0.2, 01:36:40, FastEthernet0/1
0 10.10.3.0/24 [110/101] via 10.10.0.2, 01:36:40, FastEthernet0/1
R1#
```

Verify the routing table of R3.

```
R3#sh ip route ospf

10.0.0.0/8 is variably subnetted, 10 subnets, 2 masks

0 10.10.5.0/24 [110/200] via 10.10.4.2, 01:25:10, FastEthernet0/1

0 10.10.16.0/24 [110/101] via 10.10.4.2, 01:24:53, FastEthernet0/1

0 10.10.17.0/24 [110/101] via 10.10.4.2, 01:24:53, FastEthernet0/1

0 10.10.18.0/24 [110/101] via 10.10.4.2, 01:24:53, FastEthernet0/1

0 10.10.19.0/24 [110/101] via 10.10.4.2, 01:24:53, FastEthernet0/1

0 10.10.20.0/24 [110/101] via 10.10.4.2, 01:24:53, FastEthernet0/1

0 10.10.21.0/24 [110/101] via 10.10.4.2, 01:24:53, FastEthernet0/1

0 10.10.22.0/24 [110/101] via 10.10.4.2, 01:24:53, FastEthernet0/1

0 10.10.23.0/24 [110/101] via 10.10.4.2, 01:24:53, FastEthernet0/1

R3#
```

Step 5: Configure GRE over IPsec using a Crypto Map on R1.

② On R1, configure the ISAKMP policy and pre-shared key.

Like site-to-site VPNs using crypto maps, GRE over IPsec also requires an ISAKMP policy configuration and pre-shared key configured.

In this lab, we will use the following parameters for the ISAKMP policy 10 on R1:

o Encryption: aes 256

o Hash: sha256

o Authentication method: pre-share key

o Diffie-Hellman group: 14

o Lifetime: 3600 seconds (60 minutes / 1 hour)

Configure ISAKMP policy 10 on R1:

```
R1#conf t
Enter configuration commands, one per line. End with CNTL/Z.
R1(config)#crypto isakmp policy 10
R1(config-isakmp)#encryption aes 256
R1(config-isakmp)#hash sha
R1(config-isakmp)#authentication pre-share
R1(config-isakmp)#group 1
R1(config-isakmp)#group 1
R1(config-isakmp)#lifetime 36000
R1(config-isakmp)#exit
R1(config-isakmp)#exit
```

Configure the pre-shared key of cisco123 on R1. This command points to the remote peer R3 G0/0/0 IP address.

```
R1(config)#crypto isakmp key cisco123 address 64.100.1.2
R1(config)#
```

On R1, configure the transform set and VPN ACL. Create a transform set called GRE-VPN using AES 256 cipher with ESP and the SHA 256 hash function.

```
R1(config)#
R1(config)#crypto ipsec transform-set GRE-VPN esp-aes 256 esp-sha-hmac
R1(cfg-crypto-trans)#
```

Unlike a site-to-site IPsec VPN, the transform must use transport mode. The mode command is used to identify the type of tunnel that will be established. The default is mode tunnel mode. However, GRE over IPsec should be configured using the mode transport command.

```
R1(cfg-crypto-trans)#mode transport
R1(cfg-crypto-trans)#exit
R1(config)#
```

Next, create a named extended ACL called GRE-VPN-ACL that makes the tunnel interface traffic interesting.

```
R1(config)#
R1(config)#ip access-list extended GRE-VPN-ACL
R1(config-ext-nacl)#permit gre host 64.100.0.2 host 64.100.1.2
R1(config-ext-nacl)#exit
R1(config)#
```

On R1, configure the crypto map and apply it to the interface. Create a crypto map called GRE-CMAP that associates the new GRE-VPN-ACL, transform set, and peer.

```
R1(config)#crypto map GRE-CMAP 10 ipsec-isakmp

% NOTE: This new crypto map will remain disabled until a peer

and a valid access list have been configured.

R1(config-crypto-map)#match address GRE-VPN-ACL

R1(config-crypto-map)#set transform-set GRE-VPN

R1(config-crypto-map)#set peer 64.100.1.2

R1(config-crypto-map)#exit

R1(config)#
```

Finally, assign a crypto map called GRE-MAP on G0/0/0

```
R1(config)#int f0/0
R1(config)#int f0/0
R1(config-if)#crypto map GRE-CMAP
R1(config-if)#e
R1(config)#x
*Mar 1 02:18:30.555: %CRYPTO-6-ISAKMP_ON_OFF: ISAKMP is ON
R1(config)#
```

On R1, configure the GRE tunnel interface. Configure a GRE tunnel interface as shown. To enable GRE on the tunnel interface, the tunnel mode gre ipv4 command is required. However, this command is enabled by default and will therefore not be configured in our example.

```
R1(config)#int Tunnel 1
R1(config-if)#b
*Mar 1 02:19:42.207: %LINEPROTO-5-UPDOWN: Line protocol on Interface Tunnel1, changed state t
o down
R1(config-if)#ban
% Incomplete command.
R1(config-if)#bandwidth 4000
R1(config-if)#ip add 172.16.1.1 255.255.255.252
R1(config-if)#ip mtu 1400
R1(config-if)#tunnel source 64.100.0.2
R1(config-if)#tunnel destination 64.100.1.2
R1(config-if)#end
R1#
     1 02:20:57.979: %LINEPROTO-5-UPDOWN: Line protocol on Interface Tunnel1, changed state t
*Mar
о ир
*Mar
     1 02:20:58.211: %SYS-5-CONFIG_I: Configured from console by console
R1#
```

Step 6: Configure GRE over IPsec using a Tunnel IPsec Profile on R3. In this part, we will configure GRE over IPsec using tunnel IPsec profiles on R3.

② On R3, configure the ISAKMP policy, pre-shared key, and transform set. In this step, we will configure the same parameters for the ISAKMP policy 10 that we configured on R1.Configure ISAKMP policy 10 on R3:

```
R3#conf t
Enter configuration commands, one per line. End with CNTL/Z.
R3(config)#crypto isakmp policy 10
R3(config-isakmp)#necryption aes 256

% Invalid input detected at '^' marker.

R3(config-isakmp)#encryption aes 256
R3(config-isakmp)#hash sha
R3(config-isakmp)#authentication pre-share
R3(config-isakmp)#group 1
R3(config-isakmp)#lifetime 3600
R3(config-isakmp)#exit
R3(config-isakmp)#exit
```

Configure the pre-shared key of cisco123 on R1. This command points to the remote peer R3 G0/0/0 IP address.

```
R3(config)#
R3(config)#crypto isakmp key cisco123 address 64.100.0.2
R3(config)#
```

Create a new transform set called GRE-VPN using the same security parameters and transport mode that we configured on R1. Also configure the mode transport command.

```
R3(config)#
R3(config)#crypto ipsec transform-set GRE-VPN esp-aes 256 esp-sha-hmac
R3(cfg-crypto-trans)#mode transport
R3(cfg-crypto-trans)#exit
R3(config)#
```

On R3, configure the IPsec profile. Instead of a crypto map, we will configure an IPsec profile called GRE-PROFILE using the crypto ipsec profile ipsec-profile-name global configuration command.

```
R3(ctg-crypto-trans)#exit
R3(config)#crypto ipsec profile GRE-profile
R3(ipsec-profile)#
```

In IPsec profile configuration mode, specify the transform set to be negotiated using the set transform-set transform-set-name command. Multiple transform sets can be specified in order of priority. The fist transform-set-name specified is the highest priority.

```
R3(ipsec-profile)#set transform-set GRE-VPN
R3(ipsec-profile)#exit
R3(config)#
```

On R3, configure the tunnel interface. On R3, configure a GRE tunnel interface.

```
R3(config)#int Tunnel 1
R3(config-if)#band
*Mar 1 02:21:02.023: %LINEPROTO-5-UPDOWN: Line protocol on Interface Tunnel1, changed state t
o down
R3(config-if)#bandwidth 4000
R3(config-if)#ip add 172.16.1.2 255.255.252
R3(config-if)#ip mtu 1400
R3(config-if)#tunnel source 64.100.1.2
R3(config-if)#tunnel destination 64.100.0.2
R3(config-if)#
*Mar 1 02:22:08.303: %LINEPROTO-5-UPDOWN: Line protocol on Interface Tunnel1, changed state t
o up
R3(config-if)#
```

Apply the IPsec profile GRE-PROFILE to the Tunnel 1 interface using the tunnel protection ipsec profile profile-name command.

```
o up
R3(config-if)#tunnel protection ipsec profile GRE-profile
R3(config-if)#
*Mar 1 02:22:59.715: %CRYPTO-6-ISAKMP_ON_OFF: ISAKMP is ON
R3(config-if)#end
R3#
*Mar 1 02:23:02.047: %SYS-5-CONFIG_I: Configured from console by console
R3#
```

On R1 and R3, enable OSPF routing on the tunnel interface. Verify that the GRE over IPsec VPN is operational. On R1, perform an extended ping to the R3 10.10.16.1 interface

```
R1#ping 10.10.16.1 source 10.10.0.1

Type escape sequence to abort.

Sending 5, 100-byte ICMP Echos to 10.10.16.1, timeout is 2 seconds:

Packet sent with a source address of 10.10.0.1
!!!!!

Success rate is 100 percent (5/5), round-trip min/avg/max = 20/31/44 ms
R1#
```

The pings are successful, and it appears that the VPN is operational. On R1, verify the IPsec SA encrypted and decrypted statistics.

```
R1#sh crypto ipsec sa | include encrypt | decrypt
#pkts decaps: 0, #pkts decrypt: 0, #pkts verify: 0
R1#
```

From D1, trace the path taken to the R3 10.10.16.1 interface.

```
D1#trace 10.10.16.1

Type escape sequence to abort.

Tracing the route to 10.10.16.1

1 10.10.0.1 8 msec 8 msec 12 msec
2 64.100.0.1 20 msec 28 msec 20 msec
3 64.100.1.2 24 msec 36 msec 20 msec
4 10.10.4.2 60 msec 40 msec 16 msec

D1#
```

On R1, configure OSPF to advertise the tunnel interfaces.

```
R1#
R1#conf t
Enter configuration commands, one per line. End with CNTL/Z.
R1(config)#router ospf 123
R1(config-router)#neetwork 172.16.1.0 0.0.0.3 area 0
% Invalid input detected at '^' marker.
R1(config-router)#network 172.16.1.0 0.0.0.3 area 0
R1(config-router)#
```

On R3, configure OSPF to advertise the tunnel interfaces.

```
R3#

*Mar 1 02:23:02.047: %SYS-5-CONFIG_I: Configured from console by console

R3#conf t

Enter configuration commands, one per line. End with CNTL/Z.

R3(config)#router ospf 123

R3(config-router)#network 172.16.1.0 0.0.0.3 area 0

R3(config-router)#

*Mar 1 02:29:18.111: %OSPF-5-ADJCHG: Process 123, Nbr 1.1.1.1 on Tunnel1 from LOADING to FULL
, Loading Done

R3(config-router)#
```

Step 7: Verify the GRE over IPsec Tunnel on R1 and R3

Now that the GRE over IPsec has been configured, we must verify that the tunnel interfaces are correctly enabled, that the crypto session is active, and then generate traffic to confirm it is traversing securely over the IPsec tunnel.

② On R1 and R3, verify the tunnel interfaces. Use the show interfaces tunnel 1 command to verify the interface settings

```
R1#
*Mar  1 02:37:58.139: %SYS-5-CONFIG_I: Configured from console by console
R1#sh interfaces tunnel 1
Tunnel1 is up, line protocol is up
  Hardware is Tunnel
  Internet address is 172.16.1.1/30
  MTU 1514 bytes, BW 4000 Kbit/sec, DLY 500000 usec,
     reliability 255/255, txload 1/255, rxload 1/255
  Encapsulation TUNNEL, loopback not set
  Keepalive not set
  Tunnel source 64.100.0.2, destination 64.100.1.2
  Tunnel protocol/transport GRE/IP
    Key disabled, sequencing disabled
    Checksumming of packets disabled
  Tunnel TTL 255
  Fast tunneling enabled
  Tunnel transmit bandwidth 8000 (kbps)
  Tunnel receive bandwidth 8000 (kbps)
  Last input 00:00:01, output 00:00:06, output hang never
  Last clearing of "show interface" counters never
  Input queue: 0/75/0/0 (size/max/drops/flushes); Total output drops: 0
  Queueing strategy: fifo
  Output queue: 0/0 (size/max)
  5 minute input rate 0 bits/sec, 0 packets/sec
  5 minute output rate 0 bits/sec, 0 packets/sec
     17 packets input, 2116 bytes, 0 no buffer
     Received 0 broadcasts, 0 runts, 0 giants, 0 throttles
     0 input errors, 0 CRC, 0 frame, 0 overrun, 0 ignored, 0 abort
     26 packets output, 2944 bytes, 0 underruns
     0 output errors, 0 collisions, 0 interface resets
     0 output buffer failures, 0 output buffers swapped out
R1#
R1#
R1#
```

On R3, use the show interfaces tunnel 1 command to verify the interface settings.

```
R3#sh inter tunnel 1 | include is up | Internet address |Enc | Tunnel protocols
Tunnel1 is up, line protocol is up
   Internet address is 172.16.1.2/30
R3#
R3#sh inter tunnel 1 | include is up | Internet address |Enc | Tunnel protocol
Tunnel1 is up, line protocol is up
   Internet address is 172.16.1.2/30
   Tunnel protocol/transport GRE/IP
R3#
```

On R1 and R3, verify the crypto settings.

On R1, use the show crypto session command to verify the operation of the VPN tunnel.

On R3, use the show crypto session command to verify the operation of the VPN tunnel.

```
R3#sh crypto session
Crypto session current status

Interface: Tunnel1
Session status: UP-ACTIVE
Peer: 64.100.0.2 port 500

IKE SA: local 64.100.1.2/500 remote 64.100.0.2/500 Active
IPSEC FLOW: permit 47 host 64.100.1.2 host 64.100.0.2

Active SAs: 2, origin: crypto map
```

On R1 and R3, verify OSPF routing.

On R1 and R3, verify which interfaces are configured for OSPF using the show ip ospf interface brief command.

```
R1#sh ip ospf int bri
Interface
           PID
                 Area
                                  IP Address/Mask
                                                     Cost State Nbrs F/C
Tu1
            123
                  0
                                  172.16.1.1/30
                                                     250
                                                          P2P
                                                                1/1
Fa0/1
            123
                  0
                                  10.10.0.1/30
                                                     100
                                                          DR
                                                                1/1
R1#
R3#sh ip ospf int bri
            PID Area
                                  IP Address/Mask
Interface
                                                    Cost State Nbrs F/C
Tu1
            123
                  0
                                  172.16.1.2/30
                                                     250
                                                          P2P
                                                                1/1
Fa0/1
            123
                  0
                                  10.10.4.1/30
                                                     100
                                                          DR
                                                                1/1
R3#
```

On R1 and R3, verify the OSPF neighbours using the show ip ospf interface brief command.

```
R3#sh ip ospf neighbor
                Pri
                                      Dead Time
Neighbor ID
                      State
                                                   Address
                                                                   Interface
                      FULL/
                                                                   Tunnel1
1.1.1.1
                  0
                                      00:00:36
                                                   172.16.1.1
                                                                   FastEthernet0/1
3.3.3.2
                      FULL/BDR
                                      00:00:30
                                                   10.10.4.2
R3#
R1#sh ip ospf neighbor
Neighbor ID
                      State
                                      Dead Time
                                                   Address
                                                                   Interface
                                      00:00:34
                                                   172.16.1.2
3.3.3.1
                  0
                      FULL/
                                                                   Tunnel1
                      FULL/BDR
1.1.1.2
                                                   10.10.0.2
                                      00:00:30
                                                                   FastEthernet0/1
R1#
```

Verify the R1 routing table for OSPF routes.

Verify the R3 routing table for OSPF routes.

Verify that there is an operational logical point-to-point link between R1 and R3 using the GRE tunnel interface.

Test the GRE over IPsec VPN tunnel.

From D1, trace the path taken to the R3 10.10.16.1 interface.

```
D1#trace 10.10.16.1

Type escape sequence to abort.

Tracing the route to 10.10.16.1

1 10.10.0.1 20 msec 24 msec 16 msec
2 172.16.1.2 44 msec 40 msec 24 msec
3 10.10.4.2 36 msec 60 msec 32 msec

D1#
```

On R1, verify the IPsec SA encrypted and decrypted statistics.

```
R1#sh crypto ipsec sa | include encrypt | decrypt
#pkts decaps: 100, #pkts decrypt: 100, #pkts verify: 100
R1#
```

The output verifies that the GRE over IPsec VPN tunnel is properly encrypting traffic between both sites. The packets encrypted include the trace packets along with OSPF packet